

**QUANTITY SHEET**

Local Authority :- Pradeshiya Sabhawa welimada  
 Project Name :- Construction of new building of Aurwedha center, Divithotawela, Welimada  
 Allocation :-  
 Estimate Amount :-Rs 1,999,421.11 Year :- 2025

| ITEM No | BSR CODE                        | DESCRIPTION   | UNIT           | T  | L     | W     | H     | Qty  | TOTAL QTY |
|---------|---------------------------------|---|----------------|----|-------|-------|-------|------|-----------|
| 1.00    | <b>Construction of building</b> |   |                |    |       |       |       |      |           |
|         | <b>B</b>                        | <b>B - EXCAVATOR</b>  |                |    |       |       |       |      |           |
| 1.01    | B-02                            | Excavation for Foundation in any material except rock requiring blasting, levelling and well ramed under foundation.materials within the site as directed -Depth 0~1.5m (Bank volume).  | m <sup>3</sup> | 6  | 0.75  | 0.75  | 0.750 | 2.53 | 2.53      |
| 1.02    | B-14                            | Filling under floors by spreading, watering and compacting with approved quality earth/gravel/sand in 75mm layers by manually as directed (earth/gravel/sand available at site) - Compacted volume. (Less than 50 m <sup>3</sup> .) | m <sup>3</sup> | 1  | 7.20  | 4.20  | 0.300 | 9.07 | 9.07      |
|         | <b>C</b>                        | <b>C - CONCRETER</b>  |                |    |       |       |       |      |           |
| 1.03    | C-31                            | Mixing, placing, vibrating and curing 1:2:4(20mm) concrete in column footings (Hand mixing).  | m <sup>3</sup> | 6  | 0.75  | 0.75  | 0.15  | 0.50 | 0.50      |
| 1.04    | C-33                            | Mixing, placing, vibrating and curing 1:2:4(20mm) concrete in column shafts (Hand mixing).  | m <sup>3</sup> | 6  | 0.225 | 0.225 | 0.45  | 0.13 | 0.13      |
| 1.05    | C-35                            | Mixing, placing, vibrating and curing 1:2:4(20mm) concrete in beams (Hand mixing).  | m <sup>3</sup> | 4  | 3.78  | 0.225 | 0.225 | 0.76 | 0.76      |
|         |                                 |   |                | 2  | 7.20  | 0.225 | 0.225 | 0.72 | 0.72      |
|         |                                 |   |                | 1  | 2.25  | 0.225 | 0.225 | 0.11 | 0.11      |
|         |                                 |   |                |    |       |       |       | 1.59 | 1.59      |
| 1.06    | C-39                            | Mixing, placing, vibrating and curing 1:2:4(20mm) concrete in slabs (Hand mixing).  | m <sup>3</sup> | 1  | 1.20  | 0.450 | 0.100 | 0.05 | 0.05      |
|         |                                 |   |                | 1  | 1.00  | 0.450 | 0.100 | 0.04 | 0.04      |
|         |                                 |   |                |    |       |       |       | 0.09 | 0.09      |
|         |                                 | D.D.T   |                | 1  | 0.45  | 0.450 | 0.100 | 0.02 | 0.02      |
|         |                                 |   |                |    |       |       |       | 0.02 | 0.02      |
|         |                                 |   |                |    |       |       |       | 0.07 | 0.07      |
|         | <b>D</b>                        | <b>D - FORMWORK</b>   |                |    |       |       |       |      |           |
| 1.07    | D-01                            | Supplying, fabricating, fixing and removing formwork using 25mm thick local timber planks for Column Footings.  | m <sup>2</sup> | 24 | 0.75  |       | 0.15  | 2.70 | 2.70      |
| 1.08    | D-02                            | Supplying, fabricating, fixing and removing formwork using 25mm thick local timber planks for Column Shafts.  | m <sup>2</sup> | 24 | 0.225 |       | 0.45  | 2.43 | 2.43      |

අනුමාන කරමි.

*(Signature)*

වෛද්‍ය එම්.ඩී.එස්.කරුණාරත්න  
 ලාභී පළාත් පාලනවිද්‍ය කොමසාරිස්  
 පාලනවිද්‍ය දෙපාර්තමේන්තුව  
 දිගහලාභ. 2025/07/17

|      |      |   |                |     |       |                 |         |         |        |
|------|------|---|----------------|-----|-------|-----------------|---------|---------|--------|
| 1.09 | D-03 | Supplying, fabricating, fixing and removing formwork using 25mm thick local timber planks for Beams.  | m <sup>2</sup> | 8   | 3.780 |                 | 0.225   | 6.80    |        |
|      |      |   |                | 4   | 7.200 |                 | 0.225   | 6.48    |        |
|      |      |   |                | 2   | 2.250 |                 | 0.225   | 1.01    |        |
|      |      |   |                |     |       |                 |         | 14.29   | 14.29  |
| 1.10 | D-07 | Supplying, fabricating, fixing and removing formwork using 25mm thick local timber planks for Slabs.  | m <sup>2</sup> | 1   | 1.20  | 0.45            |         | 0.54    |        |
|      |      |   |                | 1   | 1.00  | 0.45            |         | 0.45    |        |
|      |      |   |                |     |       |                 |         | 0.99    |        |
|      |      | D.D.T   |                | 1   | 0.45  | 0.45            |         | 0.200   |        |
|      |      |   |                |     |       |                 |         | 0.200   |        |
|      |      |   |                |     |       |                 |         | 0.79    | 0.79   |
|      | E    | <b>E - REINFORCEMENT</b>  |                |     |       |                 |         |         |        |
| 1.11 | E-01 | Supplying, cutting, bending, laying and binding (with 16 BWG binding wires) Mild Steel Reinforcement to slabs, beams, lintels, columns, stair cases, etc (Diameter equal to 6mm). | kg             | 230 | 0.800 |                 |         | 183.84  |        |
|      |      |   |                |     |       |                 |         | 183.84  |        |
|      |      |   |                |     |       | 183.840         | X 0.222 | 40.810  | 40.81  |
| 1.12 | E-03 | Supplying, cutting, bending, laying and binding (with 16 BWG binding wires) Tor Steel Reinforcement to slabs, beams, lintels, columns, stair cases, etc.                          | kg             | 24  | 0.900 |                 |         | 21.60   |        |
|      |      |   |                | 48  | 0.650 |                 |         | 31.20   |        |
|      |      |   |                | 16  | 3.680 |                 |         | 58.88   |        |
|      |      |   |                | 8   | 7.100 |                 |         | 56.80   |        |
|      |      |   |                | 4   | 2.150 |                 |         | 8.60    |        |
|      |      |   |                | 4   | 1.100 |                 |         | 4.40    |        |
|      |      |   |                | 4   | 0.900 |                 |         | 3.60    |        |
|      |      |   |                | 14  | 0.350 |                 |         | 4.90    |        |
|      |      |   |                |     |       |                 |         | 189.98  |        |
|      |      |   |                |     |       | 189.980         | X 0.617 | 117.210 | 117.21 |
|      | F    | <b>F - BRICK / CEMENT BLOCK WORK</b>  |                |     |       |                 |         |         |        |
| 1.13 | F-24 | 100 mm thick solid cement block in 1:5 cement sand mortar. (Size of the cement block should be L=390mm x W=100mm x H=190mm)   | m <sup>2</sup> | 2   | 5.700 |                 | 2.720   | 31.00   |        |
|      |      |   |                | 3   | 3.750 |                 | 2.720   | 30.60   |        |
|      |      |   |                | 3   | 3.750 | (3.725-2.720)/2 |         | 5.65    |        |
|      |      |   |                | 1   | 2.250 |                 | 2.720   | 6.12    |        |
|      |      |   |                |     |       |                 |         | 73.37   |        |
|      |      | D.D.T   |                | 4   | 1.200 |                 | 1.200   | 5.76    |        |
|      |      |   |                | 1   | 0.450 |                 | 0.450   | 0.20    |        |
|      |      |   |                | 1   | 1.000 |                 | 2.100   | 2.10    |        |
|      |      |   |                | 1   | 0.850 |                 | 1.950   | 1.65    |        |
|      |      |   |                | 1   | 0.750 |                 | 1.800   | 1.35    |        |
|      |      |   |                | 1   | 1.200 |                 | 2.100   | 2.52    |        |
|      |      |   |                |     |       |                 |         | 13.58   |        |
|      |      |   |                |     |       |                 |         | 59.79   | 59.79  |
|      | H    | <b>H - PAVIOR</b>   |                |     |       |                 |         |         |        |
| 1.14 | H-09 | 75mm thick concrete floor in 1:3:6(25mm) cement concrete.   | m <sup>2</sup> | 1   | 4.050 | 1.500           |         | 6.07    |        |
|      |      |   |                | 1   | 3.750 | 3.000           |         | 11.25   |        |
|      |      |   |                | 1   | 2.250 | 2.250           |         | 5.06    |        |
|      |      |   |                | 1   | 2.250 | 1.350           |         | 3.03    |        |
|      |      |   |                |     |       |                 |         | 25.410  | 25.41  |

අනුමත කරමි.

*Handwritten signature*

.....  
 ටෙනන්ට් ජී.පී.එස්.කරුණාතිත්ත  
 පාඨ පළාත් ආයුර්වේද කොමසාරිස්  
 ආයුර්වේද දෙපාර්තමේන්තුව  
 දිගමුල්ල.

2025/07/17

| J    |      | J- TILER   |                |   |        |       |  |      |        |
|------|------|--|----------------|---|--------|-------|--|------|--------|
| 15   | J-01 | Supplying and laying 300mmx600mm Glazed Ceramic Wall Tiles with exceptional quality, including 12mm thick tile bedding in 1:3 cement sand mortar and pointing with tile grout similar to the colour of tiles.(Colour, pattern and the quality should be approved by the engineer).Price range Rs.449.00-Rs.599.00  | m <sup>2</sup> |   |        |       |  |      |        |
|      |      |  |                | 2 | 1.35   |       |  | 1.20 | 3.24   |
|      |      |  |                | 2 | 2.25   |       |  | 1.20 | 5.40   |
|      |      |  |                | 1 | 1.20   | 0.45  |  |      | 0.54   |
|      |      |  |                | 1 | 1.00   | 0.45  |  |      | 0.45   |
|      |      |  |                |   |        |       |  |      | 9.63   |
|      |      | D.D.T  |                | 1 | 0.75   |       |  | 1.20 | 0.90   |
|      |      |  |                | 1 | 0.45   | 0.45  |  |      | 0.20   |
|      |      |  |                |   |        |       |  |      | 1.10   |
|      |      |  |                |   |        |       |  |      | 8.53   |
|      |      |  |                |   |        |       |  |      | 8.53   |
| 1.16 | R/A  | Laying available 600mmx300mm Homogeneous Floor Tiles with exceptional quality, including 12mm thick tile bedding in 1:3 cement sand mortar and pointing with tile grout similar to the colour of tiles.(Colour, pattern and the quality should be approved by the engineer)  | m <sup>2</sup> |   |        |       |  |      |        |
|      |      |  |                | 1 | 3.75   | 3.00  |  |      | 11.25  |
|      |      |  |                | 1 | 2.25   | 2.25  |  |      | 5.06   |
|      |      |  |                | 1 | 2.25   | 1.35  |  |      | 3.03   |
|      |      |  |                |   |        |       |  |      | 19.340 |
|      |      |  |                |   |        |       |  |      | 19.34  |
|      | K    | K-ROOFER   |                |   |        |       |  |      |        |
| 1.17 | K-11 | Supplying and roofing with 0.47mm thick colour coated Zink Aluminum metal roofing sheets on class 1 or above timber frame consist of 100mmx50mm rafters and 50mmx50mm bearers with maximum spacing of 1200mm centre to centre. ( Quality of timber and Brand, Profile and Colour of the sheets should be approved by the engineer).  | m <sup>2</sup> |   |        |       |  |      |        |
|      |      |  |                | 2 | 9.000  | 3.600 |  |      | 64.80  |
|      |      |  |                |   |        |       |  |      | 64.80  |
|      |      |  |                |   |        |       |  |      | 64.80  |
| 1.18 | K-33 | Supplying and fixing 0.47mm thick Zink Aluminum ridge capping of girth 470mm to match the colour of the roof. Rate shall include all necessary fasteners, etc.   | m              |   |        |       |  |      |        |
|      |      |  |                | 1 | 11.700 |       |  |      | 11.70  |
|      |      |  |                |   |        |       |  |      | 11.70  |
|      |      |  |                |   |        |       |  |      | 11.70  |
|      | L    | L - CARPENTER AND JOINER   |                |   |        |       |  |      |        |
| 1.19 | L-11 | Supplying and fixing 25mm thick paneled door sash in Mahogani timber with 100x75mm frame in special class timber complete with brass or equivalent approved quality furniture including 2nr of 150mm long Barrel bolt and one coat of wood primer and two coats of enamel painting to wood work. I Type and brand of door lock to be decided according to type ofwork and to be paid separately) | m <sup>2</sup> |   |        |       |  |      |        |
|      |      |  |                | 1 | 0.85   |       |  | 1.80 | 1.53   |
|      |      |  |                | 1 | 0.75   |       |  | 1.80 | 1.35   |
|      |      |  |                |   |        |       |  |      | 2.88   |
|      |      |  |                |   |        |       |  |      | 2.88   |

අනුමත කරමි.

*S. Lawo*

වෛද්‍ය එම්.පී.එස්.කරුණාරත්න  
 උඩ පළාත් ආපුරවේද කොමසාරිස්  
 ආපුරවේද දෙපාර්තමේන්තුව  
 දියතලාව.

2025/07/17

|      |       |  |                |   |        |                 |       |       |       |       |
|------|-------|--|----------------|---|--------|-----------------|-------|-------|-------|-------|
| 1.20 | L-13  | Supplying and fixing 25mm thick paneled door sash in Mahogany timber with 100x75mm frame with top louvers in special class timber complete with brass or equivalent approved quality furniture including 2nr of 150mm long Barrel bolt and one coat of wood primer and two coats of enamel painting to wood work. ( Type and brand of door lock to be decided according to type of work and to be paid separately) | m <sup>2</sup> | 1 | 1.00   |                 | 2.10  | 2.10  | 2.10  | 2.10  |
|      |       |  |                |   |        |                 |       | 5.76  | 5.76  |       |
| 1.21 | L-21  | Supplying and fixing 25mm thick timber paneled and 3mm thick glazed window in special class timber with 100x75mm frame with top louvers in special class timber complete with brass or equivalent approved quality furniture, casement fasteners, casement stays, window ring, etc. including one coat of wood primer and two coats of enamel painting to wood work.   | m <sup>2</sup> | 4 | 1.20   |                 | 1.20  | 5.76  | 5.76  | 5.76  |
|      |       |  |                |   |        |                 |       | 0.20  | 0.20  | 0.20  |
| 1.22 | L-20  | Supplying and fixing 25mm thick timber paneled and 3mm thick glazed window in special class timber with 100x75mm frame in special class timber complete with brass or equivalent approved quality furniture, casement fasteners, casement stays, window ring, etc. including one coat of wood primer and two coats of enamel painting to wood work.  | m <sup>2</sup> | 1 | 0.45   |                 | 0.45  | 0.20  | 0.20  | 0.20  |
| 1.23 | L-37  | Supplying and fixing 100x75 mm class I timber as directed including treating with approved quality wood preservative   | m              | 2 | 7.800  |                 |       | 15.60 |       |       |
|      |       |  |                | 1 | 5.100  |                 |       | 5.10  |       |       |
|      |       |  |                |   |        |                 |       | 20.70 | 20.70 | 20.70 |
| 1.24 | L-40  | Supplying and fixing 150x50 mm class I timber as directed including treating with approved quality wood preservative   | m              | 1 | 11.700 |                 |       | 11.70 |       |       |
|      | R     | R - PLASTERER  |                |   |        |                 |       | 11.70 | 11.70 | 11.70 |
| 1.25 | R-01  | 16mm thick semi rough plaster for walls in 1:5 cement sand mix finished using trowel   | m <sup>2</sup> | 2 | 4.05   |                 | 2.720 | 22.03 |       |       |
|      |       |  |                | 2 | 4.05   | (3.725-2.720)/2 |       | 4.07  |       |       |
|      |       |  |                | 2 | 5.70   |                 | 2.720 | 31.00 |       |       |
|      |       |  |                |   |        |                 |       | 57.10 |       |       |
|      | D.D.T |  |                | 4 | 1.20   |                 | 1.20  | 5.76  |       |       |
|      |       |  |                | 1 | 0.45   |                 | 0.45  | 0.20  |       |       |
|      |       |  |                | 1 | 1.00   |                 | 2.10  | 2.10  |       |       |
|      |       |  |                | 1 | 0.85   |                 | 1.95  | 1.65  |       |       |
|      |       |  |                |   |        |                 |       | 9.71  |       |       |
|      |       |  |                |   |        |                 |       | 47.39 | 47.39 | 47.39 |
| 1.26 | R-05  | 16mm thick smooth plaster for walls in 1:1:5 cement lime sand mix finished smooth with lime putty  | m <sup>2</sup> | 4 | 3.750  |                 | 2.720 | 40.80 |       |       |
|      |       |  |                | 2 | 5.700  |                 | 2.720 | 31.00 |       |       |
|      |       |  |                | 2 | 2.250  |                 | 2.720 | 12.24 |       |       |
|      |       |  |                | 4 | 5.700  | (3.725-2.720)/2 |       | 11.45 |       |       |
|      |       |  |                |   |        |                 |       | 95.49 |       |       |

අනුමත කරමි.

*S. S. S.*

සෞඛ්‍ය සේවා දෙපාර්තමේන්තුව  
 ශ්‍රී ලංකා ප්‍රජාතන්ත්‍රවාදී සමාජවාදී ජනරජයේ  
 ආදායම් දෙපාර්තමේන්තුව

දිනය: 2025/07/17

|      |        |  |    |    |      |  |      |       |       |
|------|--------|--|----|----|------|--|------|-------|-------|
|      |        | D.D.T  |    | 4  | 1.20 |  | 1.20 | 5.76  |       |
|      |        |  |    | 1  | 0.45 |  | 0.45 | 0.20  |       |
|      |        |  |    | 1  | 1.00 |  | 2.10 | 2.10  |       |
|      |        |  |    | 1  | 0.85 |  | 1.95 | 1.65  |       |
|      |        |  |    | 2  | 1.20 |  | 2.10 | 5.04  |       |
|      |        |  |    | 2  | 2.25 |  | 1.50 | 6.75  |       |
|      |        |  |    | 2  | 1.50 |  | 1.50 | 4.50  |       |
|      |        |  |    |    |      |  |      | 26.00 |       |
|      |        |  |    |    |      |  |      | 69.49 | 69.49 |
|      | S      | S - PLUMBER  |    |    |      |  |      |       |       |
| 1.27 | S-12   | Supplying and fixing 20mm (1/2") bib tap - PVC   | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.28 | S-14   | Supplying and fixing 20mm (1/2") gate valve - PVC  | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.29 | S-21   | Supplying and laying 20mm (1/2") (PNT14) or Equivalent PVC pipes with all specials rate included presure testing etc.  | m  | 12 |      |  |      | 12.00 |       |
|      |        |  |    |    |      |  |      | 12.00 | 12.00 |
|      | T      | T - SANITARY FITTINGS  |    |    |      |  |      |       |       |
| 1.30 | T-01   | Supplying and fixing 900mmx450mm approved quality stainless steel kitchen sink with single bowl and single drain board including 20mm (1/2") heavy quality chromium plated swan tap with water supply and waste water connection (Quality of sink and tap should be approved by the engineer)  | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.31 | T-12 A | Supplying and fixing ceramic closed couple water closet (Commode) with seat cover, trap, 20mm (1/2") chromium plated angle valve, flexible horse etc. to working order. Minimum 10 year warranty on ceramic ware to be available with manufacturers. (Quality approved by the engineer) Prime cost of ceramic closed couple Rs 45,000.00 | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.32 | T-17   | Supplying and fixing approved quality Chromium plated Bidet shower with 20mm (7/2") angle valve - chromium plated as directed. Prime cost of Bidet shower Rs.3,850.00 - Rs 4,500 and approved by the engineer  | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.33 | T-21   | Supplying and fixing approved quality Ceramic Soap Tray as directed (Quality should be approved by the engineer)   | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.34 | T-24   | Supplying and fixing approved quality Chromium Plated 100 mm dia. Shower Rose as directed (Quality should be approved by the engineer)   | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |
| 1.35 | T-29   | Supplying and fixing approved quality Chromium Plated 600mm Towel Rail as directed (Quality should be approved by the engineer)  | nr | 1  |      |  |      | 1.00  |       |
|      |        |  |    |    |      |  |      | 1.00  | 1.00  |

අනුමත කරමි.

*[Signature]*

සෞඛ්‍ය සේවා දෙපාර්තමේන්තුව  
 පළාත් සෞඛ්‍ය සේවා කොමසාරිස්  
 කොටුමුල්ල

2025/07/17

|      |      |  |    |  |  |  |  |      |      |
|------|------|--|----|--|--|--|--|------|------|
|      | W    | W - DRAIN LAYER  |    |  |  |  |  |      |      |
| 1.36 | W-04 | Construction of Waste water catch pits (internal size 300x300mm) depth up to 300mm with 75mm thick base in 1:3:6(25) concrete, 115mm thick brick walls and rendering in 1:3 cement sand mix including forming channel and 50 mm thick removable concrete cover in 1:2:4(20) concrete reinforced with R6@75mm c/c both ways and plastered all exposed surfaces with 1:3 cement sand mix                       | nr |  |  |  |  | 2.00 |      |
|      |      |  |    |  |  |  |  | 2.00 | 2.00 |
|      | Y    | Y - ELECTRICAL INSTALLATION  |    |  |  |  |  |      |      |
| 1.37 | Y-01 | Supplying and fixing approved quality lamp point wired through a 10 Amp switch using 2x1/1.13mm Cu\PVC\PVC (1sq.mm) wires in fully concealed PVC conduits with all specials. surface plastic casing can be use with approved condition by the engineer. Rate shall include switch, sun box, ceiling rose, round block, holder etc. (Quality should be approved by the engineer) bulb will be paid seperately | Nr |  |  |  |  | 6.00 |      |
|      |      |  |    |  |  |  |  | 6.00 | 6.00 |
| 1.38 | Y-14 | Supplying and fixing approved quality Square Pin type - G /13 Amp socket outlet wired through 7/0.67mm Cu\PVC\PVC(T)-2.5sq.mm wire and 1x7/0.67mm Cu\PVC (2.5sq.mm) earth wire in fully concealed PVC conduits with all specials. surface plastic casing can be. use with approved condition. (Quality should be approved by the engineer)   | Nr |  |  |  |  | 3.00 |      |
|      |      |  |    |  |  |  |  | 3.00 | 3.00 |
| 1.39 | Y-16 | Supplying and fixing of approved quality 40 Amp single phase main switch (10kA B.C) to working order (Quality should be approved by the engineer)  | Nr |  |  |  |  | 1.00 |      |
|      |      |  |    |  |  |  |  | 1.00 | 1.00 |
| 1.40 | Y-18 | Supplying and fixing of approved quality 40 Amp/30 mA single phase RCCB (Trip switch) (10kA B.C) to working order (Quality should be approved by the engineer)   | Nr |  |  |  |  | 1.00 |      |
|      |      |  |    |  |  |  |  | 1.00 | 1.00 |
| 1.41 | Y-22 | Supplying and fixing of approved quality 8-10 way distribution board (Sunk mounted) and thermo plastic frame with door to working order. (Main switch , trip switch and circuit breakers will be paid separately) (Quality & Surface Type should be approved by the engineer)  | Nr |  |  |  |  | 1.00 |      |
|      |      |  |    |  |  |  |  | 1.00 | 1.00 |
| 1.42 | Y-25 | Supplying and fixing of approved quality 6A,10A, 16A, 20A or 32A type"C"MCB (10kA B.C) (Quality should be approved by the engineer)  | Nr |  |  |  |  | 5.00 |      |
|      |      |  |    |  |  |  |  | 5.00 | 5.00 |

අනුමැත කරමි.

අලංකාර

සේවා මිල මාසික වාර්ෂික  
 උපරි සලකුණු කළ පරිදි  
 ආයුර්වේද දෙපාර්තමේන්තුව

දිනය 2025/07/17

|      |       |  |    |   |  |  |  |  |      |      |
|------|-------|--|----|---|--|--|--|--|------|------|
| 1.43 | Y-32  | Supplying and fixing 1800mm long 50mm dia. (1.8 mm) GI earth pipe covered by pits (internal size 450x450) depth up to 600mm with 75mm thick base in 1:3:6(25) con. 115mm Tk. Brick walls and rendering in 1:3 ct. sand mix including forming channel and 50mm tk. removable con. cover in 1:2:4(20) con. reinforced with R6@75mm c/c both way and plastered all exposed surfaces with 1:3 ct. sand mix as per drawing (Must be set to at least 10 ohms Resistance) | Nr | 1 |  |  |  |  | 1.00 |      |
|      |       |  |    |   |  |  |  |  | 1.00 | 1.00 |
| 1.44 | Y-34A | Supplying and fixing approved quality 7/1.04 Cu/PVC/PVC (T) - 6 sq.mm Twin flat main wire as directed (concealing materials will be paid separately)   | m  | 4 |  |  |  |  | 4.00 |      |
|      |       |  |    |   |  |  |  |  | 4.00 | 4.00 |
| 1.45 | Y-49  | Supplying and fixing approved quality 3W LED Bulb (B22/E27)<br>Bulb should be 25000 hrs ~ 30000hrs life span and efficacy 90 lm/w ~ 120 lm/w Heat sink, noise filliter & short circuit protection should be intergrated. complete product should be branded with minimum 2 year manufactured warranty period & Without any Complaints of ROHS. (Quality should be approved by engineer)  | Nr | 6 |  |  |  |  | 6.00 |      |
|      | O     | O- OTHER   |    |   |  |  |  |  | 6.00 | 6.00 |
| 1.46 |       | Supplying and fixing 8' 0" pre cast concrete post  | Nr | 3 |  |  |  |  | 3.00 |      |
|      |       |  |    |   |  |  |  |  | 3.00 | 3.00 |

|   |  |
|---|--|
| K. U. Pathan Madhu<br>Name Signature Date | K. U. Pathan Madhu<br>Technical officer (Civil)<br>Pradeshya Sabhawa<br>Stamp<br>Wellnada. |
| Prepared By (Technical Officer)           |  |

අනුදාන කරමි.  
K. U. Pathan Madhu  
 ටෙක්නිකල් ඔෆිසර් (සිවිල්)  
 ප්‍රාදේශීය පාලන සභාවේ  
 පාලන සභාවේ  
 දිසාපාලාය.  
 2025/07/17