

04 මෙම ව්‍යාපෘතිය සඳහා පිළිගත් ප්‍රසම්පාදන ක්‍රියාවලීන් අනුගමනය කර, ගිවිසුම් ගතවීමට කටයුතු කළ යුතුය. දෙපාර්තමේන්තු විසින් අත්සන් කරන ලද ගිවිසුමේ මුල් පිටපතක් එම අවස්ථාවේදීම ගිවිසුම්ගත කොන්ත්‍රාත් සමිතියට අදාළ වැඩ විස්තරය සමඟ ලබාදිය යුතු අතර, එහි ගිවිසුමට අදාළ වැඩ විස්තරයේ මුල් පිටපතක් ගිවිසුම්ගතවී දින 07 ක් ඇතුළතදී මා වෙත යොමු කිරීමට කටයුතු කළ යුතුය. (කොන්ත්‍රාත් ව්‍යාපෘති සඳහා පමණි)

05 ව්‍යාපෘතියේ වැඩ ගිවිසුම් කාලය තුළ කාර්මික නිලධාරීන් සෘජු අධීක්ෂණය යටතේ කඩිනමින් අවසන් කිරීමට කටයුතු කළ යුතු අතර, නොවැලැක්විය හැකි හේතූන් නිසා ගිවිසුමේ සඳහන් කාල සීමාව තුළ ව්‍යාපෘතිය හෝ අදාළ වැඩ කොටස් සිදුකිරීමේ හැකියාවක් නොමැති නම් ඒ පිළිබඳව වහාම මා දැනුවත් කර, ගිවිසුම් කාලය විධිමත් අනුමැතියකින් සාධාරණ කාලයක් සඳහා දීර්ඝ කර ගතයුතු අතර, කිසිදු හේතුවක් නිසාවෙන් ඉදිරි වර්ෂය සඳහා ව්‍යාපෘතිය අවිච්ඡේද නොකළ යුතුය.

06 මුදල් කොමිෂන් සභාව මගින් නිකුත් කර ඇති 2025.05.05 දිනැති FC/PDP/01/01/2025-II දරණ ලිපියට අනුව, ව්‍යාපෘතිය සම්බන්ධයෙන් එකඟ වී ඇති විස්තරාත්මක ප්‍රමාණ පත්‍රය (BOQ), අවශ්‍ය පාර්ශවයන්ගේ දැන ගැනීම පිණිස වැඩබිම තුළ ප්‍රදර්ශනය කිරීමට කටයුතු කළ යුතුය.

07 ව්‍යාපෘතිය ක්‍රියාත්මක කිරීමට පෙර හා ව්‍යාපෘතිය ක්‍රියාත්මක කරනු ලබන කාලය තුළදී ඒ ඒ අවස්ථා දැක්වෙන ඡායාරූප සහිතව අදාළ භෞතික හා මූල්‍ය ප්‍රගතිය ලාභ පළාත් මෙහෙයුම් හා කළමනාකරණ තොරතුරු පද්ධතියට (MMIS) ඇතුළත් කිරීමට කටයුතු කළ යුතුය.

08 ව්‍යාපෘතියේ ප්‍රමිතිය හා යොදවා ඇති ද්‍රව්‍යවල සාධාරණ වටිනාකම පිළිබඳ පූර්ණ වගකීම ව්‍යාපෘතියේ අධීක්ෂණ කටයුතු සිදු කරනු ලබන කාර්මික නිලධාරී, ජ්‍යෙෂ්ඨ කාර්මික නිලධාරී හා නාගරික ඉංජිනේරු විසින් ද, ගෙවීම් නිර්දේශ කරනු ලබන නාගරික කොමසාරිස් / නාගරික ලේකම් / සහ ලේකම් විසින් ද, ගෙවීම් අනුමත කරනු ලබන ගරු නගරාධිපති / සභාපති විසින් ද දැරිය යුතුය.

09 යම් ව්‍යාපෘතියක් සඳහා මිලදී ගැනීමක් සිදු කරන්නේ නම් ඒ සඳහා විධිමත් හා පිළිගත් ප්‍රසම්පාදන ක්‍රියාවලීන් අනුගමනය කර, ගුණාත්මක භාවයෙන් ඉහල ද්‍රව්‍ය මිලදී ගත යුතු අතර, එම තොරතුරු නිවැරදිව ලේඛනගත කර සුරකුම් කළ යුතුය. තවද බිල්පත ඉදිරිපත් කිරීමේදී ප්‍රසම්පාදන කමිටු තීරණ වාර්තාවේ පිටපතක්, බිල්පතේ හා මිලදී ගන්නා ලද භාණ්ඩය/භාණ්ඩ විධිමත් පරිදි තොර ලේඛනයට ඇතුළත් කර එහි සහතික කරන ලද පිටපතක් ද සහිතව ඉදිරිපත් කළ යුතුය.

10 ව්‍යාපෘතියට අදාළ ඉදිකිරීම් සිදු කරනු ලබන භූමියේ හිමිකාරිත්වය සභාව සතු නොවන්නේ නම් හෝ වෙනත් බාහිර පාර්ශවයකට අයත්වන්නේ නම් ඉදිකිරීම් කටයුතුවලට අදාළ ලිඛිත එකඟතාවයන් ලබා නොගෙන කිසිදු ඉදිකිරීමක් නොකළ යුතු අතර, එසේ ලිඛිත එකඟතාවයන් නොමැතිව ඉදිකිරීම් කටයුතු සිදුකිරීමේදී ඇතිවිය හැකි ගැටළු සම්බන්ධයෙන් වන වගකීම මා විසින් නොදරන අතර, එය බිල්පත් පියවීමට කටයුතු නොකිරීමට හේතුවක් වන බව ද අවධානයට ලක් කළ යුතුය.

මෙම ව්‍යාපෘතියට අදාළව සියළු තොරතුරු ඇතුළත් විධිමත් ගොනුවක් පවත්වා ගෙන යායුතු අතර, ඊට සමාගාමිච්ච සෙසු පොත්පත්, ලිපි ලේඛන හා ගිණුම් වාර්තා නිසි පිරිදි පවත්වාගෙන යාම, ඒවායේ පුරුකිතභාවය සලසාදීම හා එම තොරතුරු පහසුවෙන් හඳුනාගත හැකි පරිදි පුදුසු ක්‍රමවේදයක් සකස් කර ගැනීම අත්‍යාවශ්‍ය කරුණක් සේ සලකා ඔබගේ කාර්ය මණ්ඩලය ඒ සම්බන්ධයෙන් දැනුවත් කිරීමට කටයුතු කළ යුතුය.

අප දෙපාර්තමේන්තුවේ නිලධාරීන් ව්‍යාපෘතියට අදාළ කටයුතු වරින් වර පරීක්ෂාවට ලක්කරන බැවින් ඒ සඳහා ඔවුන්ට අවශ්‍ය සහය සැලසීමට ලබාදීමට කටයුතු කළ යුතුය.

ව්‍යාපෘතියේ වැඩ අවසන් වූ වහාම ගෙවීම් කටයුතු සඳහා අදාළ නිර්දේශයන් හා අනුමැතීන් සහිතව වැඩ අවසන් වාර්තා, විනුම්පත්, බිල්පත්, ගෙවීම් වාර්තා, වැඩ අවසන් වූ පසු ලබාගත් ඡායාරූප, අවශ්‍ය අනෙකුත් ලේඛන හා සෘජු අධීක්ෂණ කටයුතු වනුවෙන් (පරිපාලන වියදම්වලින්) යම් ගෙවීමක් කළයුතු නම් ඊට අදාළ වවුචර්පත් ද නිසි පරිදි සම්පූර්ණ කර මා වෙත දිවුරුම් කළ යුතු අතර (නිසි පරිදි ඉදිරිපත් නොකරන බිල්පත් සඳහා ගෙවීම් කරනු නොලැබේ), සියළු ගෙවීම් පළාත් පාලන ජිනේරා හෝ ජ්‍යෙෂ්ඨ කාර්මික නිලධාරීන්ගේ ක්ෂේත්‍ර පරීක්ෂාවෙන් පසුව පමණක් සිදු කරනු ලැබේ. (බිල්පත් ඉදිරිපත් වීමේදී මා විසින් හඳුන්වාදී ඇති ආකෘති පමණක් භාවිතා කළ යුතුය).

ද ව්‍යාපෘතිය සාර්ථකව ඉටුකිරීම සම්බන්ධයෙන් ඔබ හා ඔබගේ කාර්ය මණ්ඩලය දක්වනු ලබන සහය ඉතා අගය කොට කමි.

Local Authority : WELIMADA PRADESHIYA SABHA  
 Project : ESTIMATE TO THE HINNARANGOLLA ROAD AT DIKKAPITIYA.  
 Project No :  
 Funding Source : PSDG.

BOQ Summary

	Amount
(a) Civil Cost	Rs 1967385.80
(b) Physical Contingencies	Rs 3103.42
(c) Engineering and Administrative Charges	Rs 3103.42
(d) Supervision Charges	Rs 29510.79
(e) V.A.T (if any)	Rs
Total	Rs 2000000.00

This Estimate provides all expenses necessary for:

For Local Authority

Prepared by  
 T.O.  
 N.M.N.J Chandrasekera  
 Technical Officer  
 S/LCS  
 Welimada Pradeshiya Sabha  
 Welimada

Checked by  
 Draughtsman/T.O.  
 T.G.Lasanthika Sandamali  
 Technical Officer  
 Technological Service(Civil)  
 Pradeshiya Sabha  
 Welimada

Approved by  
 Commisionar/Secretary  
 Date

Department of Local Government

Checked by  
 Draughtsman  
 R.M.C.N RATHNAYAKA  
 Technical Officer (Civil)  
 Department of Local Government  
 Uva Province,  
 Badulla

Recommended by  
 S.T.O.  
 W.M. UPUL SAMANTHA  
 Senior Technical Officer (Civil)  
 Special Grade  
 (Sri Lanka Technological Service)  
 Department of Local Government  
 Badulla

Certified by  
 Engineer  
 R.M.A.S. RATHNAYAKA  
 Engineer of Local Government  
 Department of Local Government  
 Provincial Council  
 Badulla

Approved by  
 Commissioner of Local Government  
 Department of Local Government  
 Badulla  
 D.M.L.H. DISSANAYAKE  
 Commissioner of Local Government  
 Department of Local Government  
 Badulla

12/31/2025  
 2000,000/-  
 25/09/29

502 / 1001  
 2025/07/28

සාලන කොමසාරිස් (ලාභ)  
 ඉංජිනේරු, පළාත් පාලන දෙපාර්තමේන්තුව  
 හාධිකාරී, පළාත් පාලන දෙපාර්තමේන්තුව  
 ස්වකාර්මික නිලධාරී (බදුල්ල/මොණරාගල)  
 කා.ද.ගැ.ස. හා අ.ක.ස.  
 කා.ද.ගැ.ස. හා අ.ක.ස.  
 කා.ද.ගැ.ස. හා අ.ක.ස.

*Concrete work*  
**ESTIMATE**  
ESTIMATE TO THE HINNARANGOLLA ROAD AT DIKKAPITIYA.  
WELIMADA PRADESHIYA SABHA


2025

S/N	BSR/HSR NO	QTY	UNIT	DESCRIPTION	RATE	AMOUNT
1.0	DR1-009	385.00 ✓	m <sup>2</sup> ✓	leveling and Trimming erth	41.30 ✓	15900.50 ✓
2.0	STI-O47	57.75 ✓	m <sup>3</sup> ✓	Mixing & laying using concrete mixer, cement concrete 1:2:4 ( 19 mm ) ( volume batching ) using crusher run aggregate ( <i>including</i> exet. Transport of aggregate & piling, including curing )	33069.46 ✓	1909761.32 ✓
3.0	SR-16	46.20 ✓	m <sup>2</sup> ✓	Supplying and fixing 25mm thick class ii timber with debonding material as shuttering including removing for road surface concrete.	217.90 ✓	10066.98 ✓
4.0	SR-14	385.00 ✓	m <sup>2</sup> ✓	Laying seperating membrane of polythene seeting before laying cement concreet for road surface	43.80 ✓	16863.00 ✓
5.0	SR-12A	130.00 ✓	m ✓	Construction joints in concrete road surface fill with 1:3 with bitumen sand mix. or fill with approved filling material (12mm thick ) 1/3 of concreet road.	113.80 ✓	14794.00 ✓
<b>Civil cost</b>					<b>1967385.80</b>	<b>1967385.80</b>

Prepared by   
**N.M.M.J. Chandrasekera**  
 Technical Officer  
 SLPS  
 Welimada Pradeshiya Sabha  
 Welimada

Checked by   
**S. Senthika Sanjivani**  
 Technical Officer  
 Technological Service (Civil)  
 Pradeshiya Sabha  
 Welimada

Recommended by 

Approved by 



සහති  
 ප්‍රාදේශීය සභාව  
 වෙලිමාදා

## Quantity Sheets

ESTIMATE TO THE HINNARANGOLLA ROAD AT DIKKAPITIYA.

ITEM	DESCRIPTION OF WORK	T	LENTH	WIDTH	HIGHT	QUANTITY	TOTAL	UNIT
1.0	leveling and Trimming erth	1	154.00	2.50		385.00	385.00	m <sup>2</sup>
2.0	Mixing & laying using concrete mixer, cement concrete 1:2:4 ( 19 mm ) ( volume batching ) using crusher run aggregate (excl. Transport of aggregate & piling, including curing)	1	154.00	2.50	0.15	57.75	57.75	m <sup>3</sup>
3.0	Supplying and fixing 25mm thick class ii timber with debonding material as shuttering including removing for road surface concrete.	2	154.00	0.15		46.20	46.20	m <sup>2</sup>
4.0	Laying seperating membrane of polythene seeting before laying cement concreet for road surface	1	154.00	2.50		385.00	385.00	m <sup>2</sup>
5.0	Construction joints in concrete road surface fill with 1:3 with bitumen sand mix or fill with approved filling material (12mm thick ) 1/3 of concreet road.	52	2.50			130.00	130.00	m

Prepared by

**R.V.N. J. Chandrasekhar**  
 Technical Officer  
 SLAS

Weligada Pradeshiya Sabha  
 Weligada

Recommended by




**R.V.N. J. Chandrasekhar**  
 සහකාර  
 පාලන සභාව  
 වෙලිගොඩ

Checked by:-

**T.G. Lasanthika Sandamali**  
 Technical Officer  
 Technological Service (Civil)  
 Pradeshiya Sabha  
 Weligada

Approved by:-



**සහකාරී  
 පාලන සභාව  
 වෙලිගොඩ**

**RATE ANALYSIS**

*Concreting of*  
**ESTIMATE TO THE HINNARANGOLLA ROAD AT DIKKAPITIYA**

RATE ANALYSIS WITH TRANSPORT OF 1:2:4(19mm)  
For 1m<sup>3</sup>

Cement 7 Km  
Metal 13 Km  
Sand 82 Km

Welimada  
Nugathalawa  
Mhiyanganaya

BASIC RATE H.S.R. ST1-047

28382.60

Transport of HSR 2025

Transport of Cement

Transport of Metal

Transport of Sand

5.65 132.30 747.50

0.90 1221.40 1099.26

0.60 4733.50 2840.10

4686.86

TOTAL

4686.86

33069.46

Prepared by

N.M.N.J Chandrasekara

Technical Officer

SLD

Welimada Pradeshiya Sabha

Recommended by

ආ.ව.ව.ව.ව.ව. ව.ව.ව.ව.ව.

සහ ජ්‍යෙෂ්ඨ  
ප්‍රාදේශීය සභාව  
වැලිමඩා

Checked by

anthika Sandamali

Technical Officer  
Technological Service (Civil)

Pradeshiya Sabha  
Welimada

Approved by

සහ ජ්‍යෙෂ්ඨ  
ප්‍රාදේශීය සභාව  
වැලිමඩා