

**DEPARTMENT OF LOCAL GOVERNMENT - UVA
QUANTITY SHEET**

Local Authority :- Pradeshiya Sabhawa welimada

Project Name :- Estimate for Concreting ~~the Remaining~~ Section of The road From Udawela Junction to Mahathenna

Allocation :- PSDG

Estimate Amount :- Rs.

Year 2025

ITEM No	HSR CODE	DESCRIPTION	UNIT	T	L	W	H	Qty	TOTAL QTY	
<i>Concrete road</i>										
1.00	DRY-009	Levelling & trimming earth : Section 01 lenth=11.4 section 02 lenth=45.60 total lenth=159.600	sq.m	1	159.600	2.400		383.040	383.04	
2.00	SR 14	Laying Seperating Membrane Of Polythene Seeting Before Laying Cement Concreat For Road Surface	sq.m	1	159.600	2.400		383.040	383.04	
3.00	SR 16	Supplying And Fixing 25mm Thick Class II Timber With Debonding Material As Shuttering Including Removing For Road Surface Concrete .	sq.m	2	159.600	0.150		47.880	47.88	
4.00	ST1 - 047	Mixing & Laying Using Concrete Mixer, Cement Concrete 1:2:4 (19 mm) (Volume Batching) Using Crusher Run Aggregate	cu.m	1	159.600	2.400	0.150	57.456	57.46	
5.00	SR 12A	Contraction joints in concreat road surface fill with 1:3 bitumen sand mix or approved filling material. (12mm thick and 1/3 of depth of concrete slab)	l.m	53	2.400			127.200	127.20	
Name						Signature				Date
Prepared By (Technical Officer)						Stamp				

T.P. Lasarukke S. Sridharani
Technical Officer
Pradeshiya Sabhawa
Welimada