


**Department of Local Government-UVA**  
**Quantity BOQ Sheet (Billow 2.00Mn)**

Local Authority	Welimada Pradeshiya Sabhawa
Project Name	Development Form Keselwaththa To Kabillegama Road.

No	(T)	(D)	(S)	Discription
01	1.00	138.50 2.45	339.32 339.32	Levelling & trimming earth : m <sup>2</sup>
02	1.00	138.50 2.45	339.32 339.32	Laying seperating membrane of polythene seeting before laying cement concreet for road surface m <sup>2</sup>
03	45.00	2.45	110.25 110.25	Contraction joints in concreet road surface fill with 1:3 bitumen sand mix or approved filling material. (12mm thick and 1/3 of depth of concrete slab) m
04	2.00	138.50 0.15	41.55 41.55	Supplying and fixing 25mm thick class ii timber with debonding material as shuttering including removing for road surface concrete . m <sup>2</sup>
05	1.00	138.50 2.45 0.15	50.90 50.90	Mixing & laying using concrete mixer, cement concrete 1:2:4 ( 19 mm ) ( volume batching ) using crusher run aggregate (Including Transport & curing ) : m <sup>3</sup>
06			PS	Special Testing

D. M. I. S. Dissanayaka		2026/02/17	D.M.I.S. Dissanayaka Technical officer (Civil) Pradeshiya Sabhawa Welimada
Name	Signature	Date	Stamp