





Department of Local Government-UVA
BOQ Sheet (Billow 2.00Mn)

Local Authority	Walimada pradeshiya Sabha		
Funding Source	PSDG		
Allocation	2 Million		
Project Name	Estimate for Concrirting the road from Rathpaha to Vadagolla		
Project Location (GPS Coordinates)	218865.12		185066.36
	Latitude		Longitudes
Contract Number	07/03/16/2026/6	Year	2025

Item No	BSR/HSR No	Discription	Qty	Unit	Rate	Amount (Rs)
1.00	DRT-009	levelling & trimming earth	337.44	sq.m	43.20	14577.41
2.00	SR 14	Laying Seperating Membrane Of Polythene Seefing Before Laying Cement Concreat For Road Surface	337.44	sq.m	43.90	14813.62
3.00	SR 16	Supplying And Fixing 25mm thick Class II Timber With Debonding Meterial As Shuttering Including Removing For Road Surface Concreate .	42.18	sq.m	239.40	10097.89
4.00	ST1 - 047	Mixing & laying using concrete mixer, cement concrete 1:2:4 (19 mm) (volume batching) using crusher run aggregate (excl. Transport of aggregate & piling,including curing) :	50.61	cu.m	37574.00	1901620.14
5.00	SR 12A	Contraction joints in concreat road surface fill with 1:3 bitumen sand mix or approved filling material. (12mm thick and 1/3 of depth of concrete slab)	110.40	l.m	122.50	13524.00
6.00	Other	Special Testing		ps	15000.00	15000.00
						1969633.06

 Signature	 Signature	 Signature	 Signature
Prepared By (Technical officer)	Checked By (Thecnical officer/ Draughtsman)	Recommended By (Commissioner / Secretary)	Approved By (Mayor / Chairman)
27/2/2026 Date	27/2/2026 Date	27/2/2026 Date	27/2/2026 Date
Stam	D.M.I.S.Dissanayaka Technical officer(CM) Pradeshiya Sabha Walimada Stam	Stam	Stam

Material to be transported from the nearest available site and rate to be adjusted according in payment report.