


**Department of Local Government-UVA**  
**Quantity BOQ Sheet (Billow 2.00Mn)**

Local Authority	Welimada Pradeshiya Sabhawa
-----------------	-----------------------------

Project Name	Development From Hewanakumbura Muthugowahinna Road
--------------	--

No	(T)	(D)	(S)	Discription
01	1.00	136.50		Levelling & trimming earth :
		2.45	334.42	
			334.42	m <sup>2</sup>
02	1.00	136.50		Laying seperating membrane of polythene seeting before laying cement concreet for road surface
		2.45	334.42	
			334.42	m <sup>2</sup>
03	44.00	2.45		Contraction joints in concreet road surface fill with 1:3 bitumen sand mix or approved filling material. (12mm thick and 1/3 of depth of concrete slab)
			107.80	
			107.80	m
04	2.00	136.50		Supplying and fixing 25mm thick class ii timber with debonding material as shuttering including removing for road surface concrete.
		0.15	40.95	
			40.95	m <sup>2</sup>
05	1.00	136.50		Mixing & laying using concrete mixer, cement concrete 1:2:4 ( 19 mm ) ( volume batching ) using crusher run aggregate (Including Transport & curing ) :
		2.45		
		0.15	50.16	
			50.16	m <sup>3</sup>
06			PS	Special Testing

D.M.I.S.Dissanayake		2026/02/17	D.M.I.S.Dissanayaka Technical officer(Civil) Pradeshiya Sabhawa Welimada
Name	Signature	Date	Stamp