


**Department of Local Government-UVA**  
**Quantity BOQ Sheet (Billow 2.00Mn)**

Local Authority	Welimada Pradeshiya Sabhawa
Project Name	Development From Udubadana Pitawaththa To Katuwekumbura Kandahaputhenna Road

No	(T)	(D)	(S)	Discription
01	1.00	137.00		Levelling & trimming earth :
		2.45	335.65	
			335.65	m <sup>2</sup>
02	1.00	137.50		Laying seperating membrane of polythene seeting before laying cement concreet for road surface
		2.45	336.87	
			336.87	m <sup>2</sup>
03	43.00	2.45		Contraction joints in concreet road surface fill with 1:3 bitumen sand mix or approved filling material. (12mm thick and 1/3 of depth of concrete slab)
			105.35	
			105.35	m
04	2.00	137.50		Supplying and fixing 25mm thick class ii timber with debonding material as shuttering including removing for road surface concrete .
		0.15	41.25	
			41.25	m <sup>2</sup>
05	1.00	137.50		Mixing & laying using concrete mixer, cement concrete 1:2:4 ( 19 mm ) ( volume batching ) using crusher run aggregate (Including Transport & curing ) :
		2.45		
		0.15	50.53	m <sup>3</sup>
			50.53	
06			PS	Special Testing

D.M.I.S. Dissanayake		2016/02/17	D.M.I.S. Dissanayaka Technical officer(Civil) Pradeshiya Sabhawa Welimada
Name	Signature	Date	Stamp